## **Test**




## Termo Switch-

Dip the evaporator sensor into a pan filled with ice water, and check for continuity between the terminals.

Cut off 1.5—-0.5°C (35—33°F) Cut in 2.5—5°C (36—41°F)

If cut off or cut in temperature is too lower too high, replace the thermo switch.



## Relay -

NOTE: All A/C system relays are similar.

- Check for continuity between terminals ① and ③.
   There should be no continuity.
- Connect a 12 V battery across terminals ② and ④.
   There should be continuity between terminals ① and ③.

